

INDUSTRY:

Mining and Minerals

LOCATION:

Southern Saskatchewan

SCOPE OF WORK:

API 650 Tank Replacement

- Demolition of existing carbon steel tank
- Repair of existing concrete slab Foundation
- CT&V provided all design engineering and drafting
- CT&V supply of all material and on-site construction of new API 650 SS tank (Annex S)
- Removal and replacement associated tank piping

QUALITY:

- Construction standard API 650 Annex S
 - RT as per API 650 (Third Party)
 - LPI as per API 650 (Third Party)
 - Vacuum Box, Corner Box and Repad test as per API 650 & CT&V procedures
- All welder tested to ASME Section IX
- Project was completed with no deficiencies
- Pickling and passivation by CT&V

SCHEDULE:

- Completed on schedule.

CONTRACT TYPE:

- Lump Sum

SPECIALTY ITEMS:

- Fabricated in location with severely limited access without affecting mill operations
- CT&V Spyder Crane utilized for tank assembly

SAFETY:

TRIF 0.00

REFERENCE CONTACT:

- Upon Request

Project Number: MB306

